



ROOM FINISH SCHEDULE

RM. NO.	NAME	FLOOR	BASE	N. WALL	E. WALL	S. WALL	W. WALL	CEILING	CLG. HT.	REMARKS
CB-1	DISC ROOM	CONC.	G.C.C.	C. BLK.	C. BLK.	C. BLK.	C. BLK.	PRE. CONC.	14'-8"	* GLAZED CONC. BLOCK.
CB-2	OFFICE	V.A.T.	VINYL	C. BLK.	C. BLK.	C. BLK.	C. BLK.	AC. T.	9'-4"	WD. PANEL ALL WALLS
CB-3	HALL	CONC.	VINYL	C. BLK.	C. BLK.	C. BLK.	C. BLK.	AC. T.	9'-0"	
CB-4	TOILET/SHOWER	V.A.T.	VINYL	C. BLK.	C. BLK.	C. BLK.	C. BLK.	AC. T.	8'-0"	
CB-5	STORAGE	CONC.	VINYL	C. BLK.	C. BLK.	C. BLK.	C. BLK.	AC. T.	8'-0"	
CB-6	ELECTRICAL	CONC.	VINYL	C. BLK.	C. BLK.	C. BLK.	C. BLK.	AC. T.	8'-0"	
CB-7	MAINTENANCE	CONC.	NONE	C. BLK.	C. BLK.	C. BLK.	C. BLK.	PBE CONC.	14'-8"	
CB-8	CHLORINE ROOM	CONC.	NONE	C. BLK.	C. BLK.	C. BLK.	C. BLK.	PBE CONC.	14'-8"	

DOOR SCHEDULE

NO.	SIZE	DR. MAT.	DR. TYPE	FR. MAT.	FR. TYPE	FR. DIV.	FR. DIV. TYPE	FR. DIV. HGT.	FR. DIV. WID.	HEAD-SILL	JAMB.	SIDE LIGHT	REMARKS
CB-1	4'-0" x 7'-0" x 1 3/4"	HM	A	HM	A	D	1	6/8	8/8	7/8			BELOW CB-16
CB-2	3'-0" x 7'-0" x 1 3/4"	HM	A	HM	A	1	6/8	8/8	7/8				
CB-3	3'-0" x 7'-0" x 1 3/4"	HM	A	HM	B	1	6/8	8/8	7/8		6" x 6'-8"		
CB-4	3'-0" x 7'-0" x 1 3/4"	HM	A	HM	A	1	6/8	8/8	7/8				
CB-5	11'-8" x 11'-2"	STL	B	STL	C	2	9/12		3/12				HAND OPERATED
CB-6	11'-8" x 11'-2"	STL	B	STL	C	2	9/12		3/12				HAND OPERATED
CB-7	3'-0" x 7'-0" x 1 3/4"	HM	A	HM	A	1	6/8	8/8	7/8				
CB-8	4'-0" x 7'-0" x 1 3/4"	HM	A	HM	A	1	6/8	8/8	7/8				

DOOR SCHEDULE

NO.	SIZE	DR. MAT.	DR. TYPE	FR. MAT.	FR. TYPE	FR. DIV.	FR. DIV. TYPE	FR. DIV. HGT.	FR. DIV. WID.	HEAD-SILL	JAMB.	SIDE LIGHT	REMARKS
CB-9	2'-8" x 7'-0" x 1 3/4"	HM	A	HM	A	4	6/8	8/8	7/8				
CB-10	3'-0" x 7'-0" x 1 3/4"	HM	A	HM	A	5	6/8	8/8	7/8				
CB-11	2'-8" x 7'-0" x 1 3/4"	HM	A	HM	A	6	6/8	8/8	7/8				
CB-12	2'-8" x 7'-0" x 1 3/4"	HM	A	HM	A	7	6/8	8/8	7/8				
CB-13	2'-8" x 7'-0" x 1 3/4"	HM	A	HM	A	7	6/8	8/8	7/8				
CB-14	3'-0" x 7'-0" x 1 3/4"	HM	A	HM	A	5	6/8	8/8	7/8				1 HR. LABEL
CB-15	2'-8" x 7'-0" x 1 3/4"	HM	C	STL	C	3	6/8	8/8	7/8				
CB-16	4'-0" x 7'-0" x 1 3/4"	HM	A	HM	D	1	6/8	8/8	7/8				ABOVE CB-1

REVISIONS

NO.	DATE	BY	REVISIONS	REMARKS
C	2/28/77	PWP	MISC. REVISIONS	
B	9/7/76	SWJ	VENTILATION & BEAM MODIFICATION	
A	7-17-76	JEC	MISC REVISIONS	
D	8/20/77	SWJ	LENGTHEN FLOOR AND REVISE TO ACCEPT DISC COVERS TO BE SUPPLIED	

DESIGNED: D.O.C.  
CHECKED: K.L.V.  
DRAWN: D.O.C.  
APPROVED: W.H.M.  
DATE: 8/20/75  
COMM.

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY REGISTERED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.  
*Karen Van Cluck*  
DATE: Aug 29, 77, REG. NO. 1159

**McCOMBS-KNUTSON ASSOCIATES, INC.**  
CONSULTING ENGINEERS ■ LAND SURVEYORS ■ SITE PLANNERS  
MINNEAPOLIS, HUTCHINSON and MARSHALL, MINNESOTA

**WASTE WATER TREATMENT FACILITIES**  
FOR  
**ELK RIVER, MINNESOTA**

SCALE AS NOTED  
BOOK PAGE  
FILE NO. 2603  
**MAIN BUILDING ARCHITECTURAL AND STRUCTURAL PLANS**  
SHEET 11 OF 31